



Standard Notes for Erosion Control Plans

1. All erosion prevention measures shall be in place, functional, and approved in accordance with the approved Erosion Prevention and Sediment Control plan prior to commencement of construction activities. All soil disturbing and construction activities shall be conducted in accordance with MMC Chapter 16.28 Erosion Control and any applicable local, state or federal requirements.
2. Alternative sediment controls must provide a discharge that is clean and free of sediment, surfactants, and other pollutants prior to entering the storm system. Approval of alternative sediment controls by the City of Milwaukie Wastewater Division Manager is required prior to installation.
3. Written spill prevention and response procedures shall be developed, maintained, and implemented on the construction site.
4. Dumping or disposal of spoil materials into any stream corridor, wetlands, surface waters or on any public or private property not specified for said purpose is prohibited.
5. Sediment and pollutants shall not be washed into storm sewers, drainage ways, or water bodies and is subject to MMC 13.14.105 (Stormwater Discharge Regulations) . Dry sweeping shall be implemented to clean up construction areas to prevent release of sediments into the storm system.
6. Disposal of sediment laden water into the wastewater system is prohibited, unless prior written approval is received from the City of Milwaukie Wastewater Division Manager. Sediment laden water shall be pumped through an approved sediment control BMP prior to disposal into the wastewater system.
7. Sawcutting slurry and debris shall be vacuumed and removed from all impervious surfaces. Vacuumed sawcutting slurry shall be properly disposed of and not discharged into the storm system.
8. Water tight trucks shall be used to transport saturated soils from the construction site.
9. Temporary stabilization and covering of soil stockpiles shall occur at the end of each work day.
10. All toxic or hazardous materials shall be properly stored, applied, and disposed.
11. An area shall be designated for washing out concrete trucks such that runoff from washing activities are contained and do not leave the site or enter the storm system.
12. Sweepings from exposed aggregate concrete shall not be washed to the street or storm system. Sweepings shall be collected and properly disposed of in the trash.
13. Paving in wet weather when paving chemicals can runoff into the storm system is prohibited.
14. Tracking of dirt and debris onto impervious surfaces, such as streets and parking lots, is prohibited. Impervious surfaces shall be kept free of dirt and debris at all times if it can be spread by traffic or can enter the storm system.
15. Gravel or dirt curb ramps are prohibited. Only wood step style curb ramps are allowed.
16. Upon completion of site restoration and approval from the City of Milwaukie Engineering Director, all temporary erosion control measures may be removed.
17. Drainage from springs or groundwater must be addressed during construction by the contractor. Discharge from groundwater encountered on the site must be clean of sediment or pollutants.
18. Areas subject to wind erosion shall use appropriate dust control measures including the application of a fine spray of water, plastic sheeting, straw mulch, or other approved measures.
19. Dates of implementation of wet weather measures are October 1st to April 30th.
20. Materials shall not be stockpiled on public streets or in the right of way for longer than immediate use.